

**MIDLAND COUNTY ROAD COMMISSION
SHOP FLOOR REPLACEMENT – ADDENDUM #2**

February 28, 2017

NOTICE TO BIDDERS:

Pricing of bids are to follow specifications denoted below:

DEMO/EXCAVATION OF EXISTING CONCRETE FLOOR

- *MCRC will saw cut existing concrete at 6' x 6' sections at a depth of 6".*
 - *Cutting will start at 3' off the perimeter of the shop walls*
 - *Contractor will be responsible for the remaining 3' along the perimeter and removal of all waste concrete from the project.*